



BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

DIVISION: BYATARAYANAPURA

SUB DIVISION: VIDYARANYAPURA

***Name of Work: Estimate for Improvements and
Asphalting to Bloom Field Garden Roads in
Ward No. 10 (Doddabommasandra),
Vidyaranyapura Sub Division.***

JOB CODE:

Estimated Cost: Rs. 19.99 Lakhs

ಬೆಂಗಳೂರು - 92.

ಬೃ.ಬೆಂ.ಮ.ಪಾ., ಬೆಂಗಳೂರು - 97.



BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of the work: Estimate for Improvements and Asphaltting to Bloom Field Garden Roads in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.

			Estimate Cost:				1999000.00		
Sl. No.	Description	Unit	No.	L	B	D	Qty	Rate	Amount
1	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 152 / Item No. 19.1/ PWD SR 2013-14	Cum							
	Desilting of Drains								
	Blue Field Garden								
	Main Road		2	121.00	0.45	0.25	27.23		
	1st Cross Road		2	200.00	0.45	0.25	45.00		
	2nd Cross Road		2	200.00	0.45	0.25	45.00		
	3rd Cross Road		2	200.00	0.45	0.25	45.00		
							162.23	65.88	10687.00
	Basic Rate	61.00							
	Area Weightage @8%	4.88							
	Total	65.88							
2	KSRRB 300-45: Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet/surface dressing and stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges complete as per specifications. MORTH chapter 3, Page No. 158 / Item No. 19.51/ PWD SR 2013-14	Sqm							
	Blue Field Garden								
	Main Road		1	121.00	5.20		629.20		
	1st Cross Road		1	200.00	5.20		1040.00		
	2nd Cross Road		1	200.00	5.20		1040.00		
	3rd Cross Road		1	200.00	5.20		1040.00		
							3749.20	40.50	151843.00
	Basic Rate	37.50							
	Area Weightage @ 8%	3.00							
	Total	40.50							

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
3	KSRRB M400-17. Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications Page No.170 / Item No. 20.18 PWD SR - 2013-14.	Cum							
	Blue Field Garden								
	Main Road		1	121.00	5.20	0.15	94.38		
	1st Cross Road		1	200.00	5.20	0.15	156.00	182.0	
	2nd Cross Road		1	200.00	5.20	0.15	156.00	182.0	
	3rd Cross Road		1	200.00	5.20	0.15	156.00		
							562.38	1121.04	630450.00
	Basic Rate	1038.00							
	Area Weightage @ 8%	83.04					614.38		6887450
	Total	1121.04							
4	KSRRB 500-1.1 : Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification No. 500-1.3 Page No. 175 / Item No. 21.1 PWDSR 2013-14	Sqm							
	Blue Field Garden								
	Main Road		1	121.00	5.20		629.20		
	1st Cross Road		1	200.00	5.20		1040.00		
	2nd Cross Road		1	200.00	5.20		1040.00		
	3rd Cross Road		1	200.00	5.20		1040.00		
							3749.20	10.53	39479.00
	Basic Rate	9.75							
	Area Weightage @ 8%	0.78							
	Total	10.53							
5	KSRRB M500-6: Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH specification NO. 502, Page No. 175 / Item No. 21.6 / PWD SR 2013-14	Sqm							
							Qty Vide Item No. 4	3749.20	
							3749.20	44.28	166015.00
	Basic Rate	41.00							
	Area Weightage @ 8%	3.28							
	Total	44.28							

(5)

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
6	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen, No. 175/ Item No. 21.20.1/ PWD SR 2013-14	Cum							
	Blue Field Garden								
	Main Road		1	121.00	5.20	0.025	15.73		
	1st Cross Road		1	200.00	5.20	0.025	26.00		
	2nd Cross Road		1	200.00	5.20	0.025	26.00		
	3rd Cross Road		1	200.00	5.20	0.025	26.00		
							93.73	9631.44	902755.00
	Basic Rate	8918.00							
	Area Weightage @ 8%	713.44							
	Total	9631.44							
7	KSRRB M800-13: Road marking with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface- providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface to level, uniform and free from streaks and holes complete as per specifications. MORTH specification No. 803, No. 197 / Item No. 24.15 PWD SR 2013-14	Sqm							
	Somanna Garden								
	Road Sides								
	Blue Field Garden								
	Main Road		2	121.00	0.10		24.20		
	1st Cross Road		2	200.00	0.10		40.00		
	2nd Cross Road		2	200.00	0.10		40.00		
	3rd Cross Road		2	200.00	0.10		40.00		
	Center Line								
	Blue Field Garden								
	Main Road		40	1.50	0.10		6.00		
	1st Cross Road		67	1.50	0.10		10.05		
	2nd Cross Road		67	1.50	0.10		10.05		
	3rd Cross Road		67	1.50	0.10		10.05		
							180.35	471.96	85118.00
	Basic Rate	437.00							
	Area Weightage @ 8%	34.96							
	Total	471.96							

Sl. No	Description	Unit	No.	L	B	D	Qty	Rate	Amount
8	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum							
						Vide Item No. 1	162.23	72.71	11795.00
	Basic rate for haulage of materials as per item no.17.4 page 141) Rs. 2.00								
	Average weight of earth 1.28 tonne / kg for 2X1.28X2.00=5.12	5.12							
	Add loading and unloading Vide item no.17.1 P.no.141	62.20							
		67.32							
	Area Weightage @ 8%	5.39							
	Total	72.71							
	1.1. T&S charges								19990
9	Miscellaneous and other Charges	L/S						7691	858.00
								Total	1999000.00

(Rs. Nineteen Lakhs Ninety Nine Thousand Only)

CERTIFICATE:

- 1 The work spot has been inspected and the work is found necessary.
- 2 This estimate is prepared as per P.W.D S.R of 2013-14.
- 3 This work included under 2013-14 POW Grant.
- 4 The provisions were made in this estimate are necessary and adequate.
- 5 This works come under B.B.M.P. limits.

[Signature]
Assistant Engineer

[Signature]
Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Vidyaranyapura Sub Division

[Signature]
Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division

ADMINISTRATIVELY SANCTIONED FOR Rs. **19.99 Lakh**

Rupees **Nineteen lakhs Ninety Nine**
- thousand only

Under **P-1771**

Registered as EE () No. **3** ...9...

Subject to conditions contained in

enclosed memo EE () No. **392/13-14**

Dt. **30/10/13** Estimate A/Sanctioned


No. **30/10/13**

dated **30/10/13** Rs. **19.99 Lakh**

[Signature]
Joint Commissioner
(Yelahanka Zone)
BBMP, Bengaluru-92


Technical Sanction for Rs. 19.99 Lakh	
Rs. Nineteen Lakh, ninety nine thousand only	
P-1771	
EE No. 178/13-14	Dated 29/10/13
Subject to conditions contained enclosed memo.	
No. 178/13-14	Dr. 29/10/13
<i>[Signature]</i> A.E.	<i>[Signature]</i> EE (DTP Div.)

Sketch for Improvements and Asphaltting to Bloom Field Garden Roads in Ward No. 10 (Doddabommasandra), Vidyaranyapura Sub Division.



Zeehan
AE

Pub
Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore - 97



CROSS-SECTION OF ROAD

INDEX

-  Wet mix macadam
-  Semi dense bituminous concrete


ASSISTANT ENGINEER


ASSISTANT EXECUTIVE ENGINEER
VIDYARANYAPURA SUB DIVISION.

152 - BYATARAYANAPURA AC
WARD NAME : 10 - DODDA BOMMASANDRA



Zeelhar
AE

padh

Assistant Executive Engineer
Vidyaranyapura Sub Division
BBMP, Bangalore - 97